



Gap 901 Cherry Street – Buildings 2 and 3 San Bruno, CA



Owner:	Gap, Inc.
Developer:	Wilson/Equity Office
Completion Date:	December 2002
Size:	290,000 ft ² office; 380,000 ft ² underground garage; 2 stories
Architects:	William McDonough + Partners Kendall/Heaton Associates, Inc.
General Contractor:	Swinerton & Walberg, Inc.
Mechanical Contractor:	Scott Co. of California
HVAC System Description:	Underfloor air distribution with variable volume and temperature perimeter system, 510 ton central chilled water plant including variable speed chillers and primary-only variable speed pumping system.
Taylor Engineering's Role:	Full design of HVAC and energy management & control systems, development and DOE-2 analysis of energy conservation measures, HVAC system and control system commissioning.
References:	Gap: Fred Kriebel (fred_kriebel@gap.com) Wilson/Equity: Terry Reagan (treagan@wilsonequity.com) McDonough: Kevin Burke (kburke@mcdonough.com) Swinerton: Dan Beyer (dbeyer@swinerton.com)