



## Palm, Inc. Campus San Jose, CA



|                            |   |
|----------------------------|---|
| Owner:                     | Palm, Inc.  |
| Completion Date:           | August 2002 (Phase 1), December 2003 (Phase 2)  |
| Size:                      | 1,600,000 ft <sup>2</sup> office; 200,000 ft <sup>2</sup> underground garage; 4 to 6 stories  |
| Architects:                | William McDonough + Partners<br>Hellmuth, Obata & Kassabaum, Inc.   |
| General Contractor:        | Webcor Builders   |
| Mechanical Contractor:     | Critchfield Mechanical, Inc.  |
| HVAC System Description:   | Underfloor air distribution with perimeter underfloor variable speed heating fan-coils, unique and highly efficient double-effect evaporative pre-cooling system and water-cooled chilled water system.   |
| Taylor Engineering's Role: | Full design of HVAC and energy management & control systems, development and DOE-2 analysis of energy conservation measures, HVAC system and control system commissioning.  |
| References:                | Palm: John Igoe ( <a href="mailto:john_igoe@palm.com">john_igoe@palm.com</a> )<br>McDonough: Kevin Burke ( <a href="mailto:kburke@mcdonough.com">kburke@mcdonough.com</a> )<br>Webcor: Andy Ball ( <a href="mailto:andy@webcor.com">andy@webcor.com</a> ) |